

S.S. "Sorka"

June 7

Sample Report

SPECIAL SURVEY NO. 1

Vessel placed in dry dock, bottom, rudder, stern frame, ^{bow} keel and stem cleaned examined and found or put in good condition, afterwards recoated.

Holds, fore and after peaks (~~and peak tanks~~) spaces under shade decks, engine and boiler space and coal bunkers cleared for survey, ~~ceiling lifted all fore and aft~~, all oxidation removed from all parts, and all steel work throughout all parts of vessel carefully examined and found or put in good condition, afterwards recoated: ~~lining on ship's side removed in way of~~

~~sidelights and plating in way of same~~ examined and found or put in good condition, ^{Deep} ~~double bottom tank and fore and after~~ ~~examined internally and~~ peak tanks tested with a head of water as required by the Rules,

decks, hatchways, hatches, ~~fore and afters~~, ceiling, cargo battens, air and sounding pipes, plates under sounding pipes, windlass, steering engine, gear rods, chains, sheaves, etc., pumps, sluice valves, w.t. doors, scuppers, skylights, boats, masts, (~~rigging removed~~) ~~spars, rigging, anchors, chain cables, (cables ranged)~~, hawsers and warps and general equipment examined and all found or put in good condition, ~~forehead verified~~.

~~NOTE~~. The outside plating may require to be drilled, but if it is not drilled the Surveyors must state that in their opinion drilling is not necessary.



W. J.

17/6/23.

Lloyd's Register
Foundation

006809-006818-0056

006809-006818-0057