

COPY.

# Lloyd's Register of Shipping.



Port of Düsseldorf.

15th July 1929.

Order P.974.

This is to Certify that

Friedrich Kohlsaat

the undersigned Surveyor to this Society did at the request of Messrs. Press- & Walzwerk A.G. of Düsseldorf-Reisholz test and inspect on the 13th July 1929 at their work the undermentioned seamless Siemens-Martin Steel air receivers, ordered by Messrs. Maschinenfabrik Augsburg-Nürnberg A.G. of Augsburg.

## Specification.

No. of rec.	Outs. diam.	Thickness of shell	Length of receivers
2	640 mm	27,5	3400 mm

## Results of tests.

Sample No.	Yield Point	Tensile ten.in kg.p.sq.mm.	Elongation in 200 mm
39	30,9	45,2	26,5%
40	29,3	44,9	27,5%

Bend tests good.

Hydraulic test: 2130 lbs.p.sq.inch.

Working pressure not to exceed: 1065 lbs.p.sq.inch.

For identification the receivers have been stamped as follows:

.....  
No.627-628  
LLOYDS TEST  
2130 lbs.  
W.P.1065 lbs..  
F.K.13.7.29..  
.....

*F. Kohlsaat*

Surveyor to Lloyd's Register

© 2020

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—  
“While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society.”