

17 320100 F6V53/53

No 1802.

m.s. Hengstler

Lloyd's Register of Shipping.

Air Receiver engine F6V53/53
to the order of H. G. Hengstler, of
Porter Düsseldorf, Gillingham, Kent.

5th February 1929.

Order: P.503.

This is to Certify that

Josef Loogen and Friedrich Kohlhaas

the undersigned Surveyors to this Society did at the request of

Press- & Walzwerk A.G. of Düsseldorf-Reisholz test and inspect on the 28th
and 31st January 1929 at their work the undermentioned seamless Siemens-
Martin Steel tubes for air receivers, ordered by Messrs. Maschinenfabrik
Augsburg-Mürnberg of Augsburg.

Specification.

No. of tubes	Outs. diam.	Thickness of shell	Length of tubes
12	440 mm	17,5 mm	3650 mm
5	440 mm	17,5 mm	3950 mm
12	440 mm	17,5 mm	3950 mm

Results of tests.

Sample No.	Yield Point in kg. p. sq. mm.	Tensile ten.	Elongation in 200 mm
1	27,4	42,9	28,7%
2	30,1	48,6	26,3%
3	30,1	43,4	27,9%
4	31,9	46,2	26,3%
5	31,4	48,6	24,6%
6	27,1	46,4	29,5%
7	30,9	47,8	24,5%
8	30,3	48,7	26,2%
9	31,9	49,2	25,7%
10	29,9	47,9	25,0%
11	31,7	48,9	26,0%
12	30,7	46,0	29,6%
13	28,1	46,9	26,2%
14	28,5	45,7	25,0%
15	27,4	46,9	26,0%
16	26,6	46,8	31,3%
17	31,6	49,6	23,7%
18	29,4	46,1	29,7%



issued upon the terms of the Rules and Regulations of the Society, which provide that:—

End sheet.

the Committee for the Society are under no responsibility whatever for the accuracy of any report or certificate issued by the Society or the Surveyors, or for any entry in the Register Book or other publication of the Society, for any error of judgment, default or negligence of the Surveyors, or other Officers or Agents.



1/2

006819-006830-008

006819-006830-008

End sheet. Order: P.503.

Sample No.	Yield Point in kg. p. sq. mm.	Tensile ten.	Elongation in 200 mm
19	28,1	45,9	27,0%
20	28,7	45,8	28,2%
21	28,2	46,6	27,5%
22	29,6	46,6	24,5%
23	31,9	49,4	26,0%
24	28,1	46,4	26,2%
25	30,4	47,0	27,2%
26	27,7	45,7	28,7%
27	31,1	46,4	27,5%
28	30,4	45,6	29,0%
29	27,8	45,4	26,0%

Bend tests good.

The tubes have not been tested by hydraulic pressure.

Identification marks: LLOYDS J.L. No.1-5 28.1.29.
LLOYDS F.K. No.6-29 31.1.29.

L. J. J. F. K. K. K.
Surveyors to Lloyd's Register



© 2020

Lloyd's Register
Foundation

0086 2/12

006819-006830-008