

R. 130.

Col 15 : { 12 " 6
 31 " 4 1/4
 11 " 2 1/2

(LLOYD'S REGISTER.)**VESSELS OF 100 TONS AND UPWARDS.**

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)..... M. J. Q. V.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
180790	FRESHPOND	375 in 1945. London

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	Lytham	1945	The Lytham Shipbuilding and Engineering Company Limited Lytham, Lancashire.

Number of Decks	One	Length from fore part of stem, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	One	Main breadth to outside of plank	121	2
Rigged	Not	Depth in hold from tonnage deck to ceiling amidships	24	7.5
Stem	Straight Raking	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	11	7.5
Stern	Elliptical	Depth from top of deck at side amidships to bottom of keel...	12	6
Build	Clincher	Round of beam	-	5
Framework and description of vessel	Steel	Length of engine room, if any	40	2.5
Number of Bulkheads	Water tank vessel Eight								

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke	No. of Cylinders in each set	
One	Triple expansion Direct acting Surface Condensing	British	1945	Engines Lytham Shipbuilding & Engineering Co. Ltd., Lytham.	Three 11" 18" 30"	21"		59 360 450 10 Knots
One	Particulars of Boilers Description Cylindrical Multitubular Number One Iron or Steel Steel Loaded Pressure 180 lbs.	British	1945	Boilers				

Number of water ballast tanks, and their capacity in tons:— Two - 34 Tons

GENERAL REMARKS—(The Surveyor should state the Number of Report and Name of any Sister Vessel. Plans showing Vessel as built should be forwarded and a List of the Plans should be embodied.)

Liverpool RPL No 121446 (RFA Freshford) sister vessel.
 The approved plans (duplicates of which are in the London office) have been retained for reference in dealing with sister vessels now under construction in the same yard.

Forging reports forwarded herewith for Stemframe, Rudder stock & main piece & tiller.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons
Under Tonnage Deck	...	261.55	On account of space required for propelling power		113.44
Space or spaces between Decks	...	-	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.		53.20
Turret or Trunk	...	-	These spaces are the following:- below deck in fore-castle and deck houses (Number of Seamen or Apprentices for whom accommodation is certified 11)		
Fore-castle	...	13.94	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-		
Bridge space	...	-	Cubic Meters. Masters Accommodation 6.14		
Poop or Break	...	-	Boatswains Store 5.66		23.45
Side Houses	...	-	Water Ballast Spaces 11.65		
Deck Houses	...	7.42	Total		190.09
Chart House	...	-			
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	...	-			
Excess of Hatchways	...	-			
Gross Tonnage	...	282.91			
Deductions, as per contra	...	190.09			
Register Tonnage	...	92.82			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 79.69 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 24.74 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

None

Particulars of Cast & Weight Number of Tons

PART I

Official

Name of Master

Certificate of Service No. Competency No.

No. and

No. of Owners

Parts of

Name, Residence, and Description of Managing Owner if there are more owners than one.

Particulars

His Majesty represented by the Commissioners for executing the Office of Lord High Admiral of the United Kingdom, London.

The Secretary of the Admiralty, Whitehall, S.W.1. designated Managing Owner, under Order in Council 22nd March, 1911.

PART II

Shares:- Sixty-four.

Dated 14th December, 1945.

Wt. 525. Gp. 39. 1,000 8/45. H.T. Ltd. W801.

Double

Double bottom, under Engines and Boilers,

After peak tank, 7'-0" 17 1/2

Double bottom, if under Engines only,

Deep tank, aft, No 1 FW tank 10'-6" 88

Double bottom, if under Boilers only,

Deep tank, forward, 2 12'-3" 102

Double bottom, forward,

Other tanks, if fitted, 3 7'-0" 46

Total length (if continuous) and Capacity

(If necessary furnish further information by sketch.)

Order for Special Survey No. 1358

Date 22/12/44

Dates of Surveys held while building

10/3/45 to 22/12/45



© 2021

Lloyd's Register Foundation Total No. of Visits 56