

Lloyd's Register of Shipping.

Ship's Name "KOMAKI MARU"

Official No. 38561

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in October, 1934.

ALTERATIONS:-

The tonnage opening hatch at the after end of the upper deck has been removed and the deck in way plated over.

The forward bulkhead of the tonnage opening space has also been removed and suitable beams and supports to weather deck fitted in way of alteration.

The freeing ports and scuppers, P&S from tonnage space have been permanently closed with plates electrically welded and riveted.

These parts and the weather deck in way of alterations hose tested and found tight.

The new freeboards assigned by the Japanese Government have been cut in and verified. See verification form herewith.

NOTE:-

The scantlings of this vessel were originally approved for the draft moulded of 27'9"

The new tonnages have not yet been claculated officially

Kobe Rpt. 8 No. 10573. Dated, 10/3/38.

Noted.
5/4/38.