

Extracts from the printed specification of the Steamer
"ETHELSTAN".

5. -General Description.

Par.2. To have flat plate keel, straight stem, and elliptical stern. To be built of steel, and to take the 100A1 Class at Lloyd's under the special survey of their inspectors.

31. -Ceiling.-

Ceiling of $2\frac{1}{2}$ " whitewood to be fitted on tank top in way of hatchways, and over limbers to upper turn of bilge, laid fore and aft. Limber boards fitted at bilges with rings for lifting as may be required. Bunkers to be close ceiled with $2\frac{1}{2}$ " wood.

85. - Generally-

Par.2.

The specification of machinery and all items to the full requirements of Lloyd's for the 100A1 Class.



© 2020

Lloyd's Register
Foundation

007008-007020-0013