

F.E.

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME *S.S. "Ville D'Amiens"* Rpt. *Bel. Bry.* No. *9228*
19449

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/32.)

Transverse No. *84.5* Depth "d" *17.75*
Framing: Table No. *3* Description *Bull angle as approved.*
Longitudinal No. *34645*

Proportions Length = *10.7*
Depth =

Deck Sheerstrake *as approved.*

Old Rules.

The vessel received damage in launching, repairs have been effected at Barry bottom cleaned & coated, 4 shell plates removed & fairied 4 fairied in place, 8 frames, 1 reverse frame 16 floors fairied in place & minor repairs.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed **✠ 100A1 (Steel) "Shelter deck"** with freeboard, as recommended. The Summer freeboard of *10' 7 3/4"* from centre of disc to top of statutory deck line at *shelter* deck, now marked on the vessel's sides, to be inserted in the classification certificate, and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying verification form to be inserted in the certificate of classification.

2 Dks (Stl.) & Shelter Dk (Stl. W.S.)
cell D.B. 351' 1160t. F.P.T. 95' A.P.T. 120t.
F.K. 7B.H. (Collision B.H. to Shelter D.) rem. Lloyd's A.P.F. 37' m. Shelter D's

It is concluded the butts of the centre girder are triple riveted but the surveyor should state if this is so.

