

Divided Certificate, Issued 29th Nov. 1934.

Lloyd's Register of Shipping.

Port

NAGASAKI.

25th October 1934.

CERTIFICATE No.1072-A.

This is to Certify that

at the request of Messrs. Mitsubishi Jukogyo Kaisha, Ltd., Nagasaki, attend at their works on the 13th September 1934, in order to examine under test, One shunt wound, direct current, 3.5 K.W. Motor, No.15185, of 220 volts, by 20.4 amps, at 2600 revolutions per minute, for Circulating Pump.

This Motor ordered by Messrs. Mitsubishi Jukogyo Kaisha, Ltd., Nagasaki, is intended for their Vessel No.582.

The Motor was submitted to the following tests:-

Full load test of 5 hours duration.
25% overload test of 2 hours duration.
50% overload test for 1 minute.

The rise of temperature was measured by thermometers and on completion of trials, high voltage (2000 volts, A.C.) and insulation tests were carried out, and all found satisfactory.

For purposes of identification the Motor has been stamped on the casing as follows:-

Motor No.15185.

LLOYD'S
No.1072-A.
TK 12-9-34

T. Kurishie
ASSIST. SURVEYOR TO LLOYD'S REGISTER.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society.