

Steel s.s. "BALTAANNIC".

-0-0-0-0-0-0-

Dimensions 242' x 37' x 18.5' to U.D.

28.75' to B.D.

Scantling Nos. 4499 &amp; 13497

Proportions 13.1' to U.Dk. and 9.4' to B.D.

This vessel was built in 1913 to Bureau Veritas classification and has not been classed with this Society.

Plans of the vessel were examined in this Office in 1920 and in June this year were compared with the revised rules with a view to recommending class 100 A- when it was found that certain additions would be required.

The Rotterdam Surveyors now forward particulars of the scantlings together with a report of the examination made.

The vessel has been placed in dry dock and the requirements of the s.s. No.3 complied with, an additional web frame fitted in the engine space and after hold and the floors etc., strengthened as required.

The equipment is in accordance with the rules but the chain cables have been tested by the B.V. Surveyors.

It is submitted the vessel appears worthy to be classed 100 A.1 (steel) with record of survey 7-25 and notation of s.s. Rot. No.3-7-25.

100 A.1 (steel)


2 dks. (stl)

Cell D.B. a &amp; U.E 72' f. 98'; 263t. F.P.T. 27t. A.P.T. 31t.

F.K. 5 B.H. Cem. P. 44' B. &amp; F. 170'

7-25 Rot.

s.s. Rot. No.3-7-25.



© 2021

Lloyd's Register  
Foundation