

s. s. "WESTLAND"

This vessel was built in 1913 by Messrs.
The Rotterdam D.D.Co and classed with the Bureau Veritas.

The Owners now desire this Society's
classification.

With steam reciprocating engines having cyls.
21½, 33 and 57 inches dia. by 39 inches stroke,
W.P. 180 lb. per sq. inch, the size of crank shaft shown
on the plan, viz- 11.1/4" dia. meets the requirements of
the Rules for the above working pressure.


The scantlings of the boiler as shown on the
plan meet the requirements of the Rules, in force at the
time the vessel was built, for the original working
pressure of 180 lb. per sq. inch.

It is submitted that provided the working parts of
the engines be opened out, examined and found in good and
safe working condition and in accordance with the Rules;
the sizes of the line shafting be such as could be approved;
the boilers be examined throughout, their scantlings
be as shown on the plan, and the boilers be found in good
and safe working condition, and the pumping arrangements be
in accordance with the requirements of the Rules, the
machinery of the vessel might be accepted for the original
working pressure of 180 lb. per sq. inch, and a notation of
LRC (with date) without the distinguishing mark * assigned.

Particulars of the line shafting and a plan
of the pumping arrangements should be submitted for
consideration.

Return 3 plans & FORWARD
BOILER PLAN TO ROT. SURS.

3. 7. 25.



Lloyd's Register
Foundation

007078-007087-0048

58 Fenchurch St
863

L 6/7/25