

# Lloyd's Register of Shipping.

Ship's Name S. S. "KRAKOW."

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in

One additional cowl ventilator has been fitted on the bridge deck starboard side between casing side and coaling hatch to ventilate a new store room which has been built in the forward end of the bridge tween deck bunker. Ventilator 6" in diameter, steel pipe coaming 30" high by 5/16" thick welded to bridge deck plating and provided with a wood plug and canvas cover. Entrance to new store room is from the existing bunker hatch on the bridge deck starboard side. No alteration has been made to the hatch coaming or closing appliances.

A copy of this report has been placed on board the vessel.

Alex. M. Jenkins  
Surveyor to Lloyd's Register of Shipping  
LONDON.  
19TH MAY 1944.

12 JUN 1944  
A.P.

