

UNCLASSIFIED SECTION 27187
East Indian 26180
Dresden Pierre Renoit 25963
Mecaministongish 25709

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.

Port of Survey Yokohama

Date of Survey 12.9.18

Name of Surveyor Jas. L. Cairns

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR
AWNING DECKS.

Wrago D. Co

MEIU MARU

" Ship's Name. ~~Meiwa Maru~~ "

Port of Registry
and Nationality.Official
Number.

Gross
Tonnage.

Date of Build.

Particulars of Classification.

+ 100 Ft. shelter deck
with freeboard

Number in Register Book

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.
	445	58.0 mld. 58.2 eo.	6 tank 29.25	6044.52
Length on LOADLINE	445	Frame Depth 11 Rule " 7	Ceiling + .70 Sheer + .50 4 1/2 drop in — .66 tank = +.16	Peak Tanks
CORRECTED DIMENSIONS.	445	57.54	30.11	6044.52

Moulded Depth as measured 32-1 ⁵/₈ Main Deck.
 " " " 40-2 ¹/₂ Sheel Spar or Awning Deck.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Co-efficient of fineness 78

Any modification necessary;

[Para. 4 (a) to (e)⁴]

Co-efficient as corrected

CORRECTION FOR LENGTH :—

Length of Ship on Load Line.....	445
Length in Table	385.62
Difference.....	59.38
Correction for 10ft.....	.8
× Difference ÷ 10 =	5.938

Allowance for strength in excess of Lloyd's rules = $12\frac{1}{2}$

State particulars—

Deep framing
strengthened lapboards
3 steel decks
6 W.T. plds. to upper dk.
1 " " to lower dk.

Height of 'Tween Decks..... 8-05/8

(From top of beam to top of beam at side)

Correction for Height of "Tween Decks in Spar-decked Ships.....

Freeboard Table B or C	5 - 3
Correction for Length.....	+ 4 $\frac{1}{2}$
	5 - 7 $\frac{1}{2}$
Correction for Height of 'Tween Decks in Spar-decked Ships.....	8 - 0 $\frac{1}{2}$
	13 - 8 $\frac{1}{2}$
Correction for Strength in excess of Lloyd's rules.....	- 1 - 0 $\frac{1}{2}$
	12 - 8
Correction for Iron Deck if required.....	- 3 $\frac{1}{2}$
	12 - 4 $\frac{1}{2}$
Other Corrections (if any).....	

Winter Freeboard.....	6½	12 - 4½
Summer Freeboard.....		11 - 10
Indian Summer Freeboard.....		11 - 3½
N. A. Winter Freeboard.....		

Correction necessary because clearside amidships measured
in accordance with the Statute is not taken at inter-
section of the ~~wood~~ or iron deck with side

Winter Freeboard from Deck Line	12-6
Summer " " "	11-11 $\frac{1}{2}$
Indian Summer " "	11-5
N.A. Winter " " "	" "

N.A. Winter " " "
 (Iron) Deck — *Shelley* 11-11 1/2"

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, ~~Wood~~ (Iron) ^{Steel} Deck :—

[illegible]

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.
All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.

* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.

c.12.16 T.

© 2020

P.T.O.

MARKING REPORT
RECEIVED 20-11-18.

Lloyd's Register
Foundation

007088-007099-0055