

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 2292

Ad how

Port of Kobe Date of First Survey 15 May Date of Last Survey 18 June No. of Visits 6
 No. in Reg. Book on the Iron or Steel S.S. "Nagato Maru" Port belonging to Tokio
 Built at Kobe By whom The Kawasaki Dockyard Co. Ltd. When built 1918
 Owners The Nippon Yusen Kaisha Owners' Address Tokio
 Yard No. 409 Electric Light Installation fitted by The Kawasaki Dockyard Co. Ltd. When fitted 1918

DESCRIPTION OF DYNAMO, ENGINE, ETC.

Two sets of compound dynamo coupled directly to single cylinder automatic cut-off vertical enclosed engine with forced lubrication.
8" dia 6" stroke 450 r.p.m.

Capacity of Dynamo 170 Amperes at 100 Volts, whether continuous or alternating current continuous

Where is Dynamo fixed in the engine room Whether single or double wire system is used double

Position of Main Switch Board in the engine room having switches to groups A, B, C, D & E of lights, &c., as below

Positions of auxiliary switch boards and numbers of switches on each 1 in engine room, 1 in boiler room, 4 on shelter deck, 1 on lower bridge and 1 on the after main, having one main switch on each board.

If fuses are fitted on main switch board to the cables of main circuit Yes and on each auxiliary switch board to the cables of auxiliary circuits Yes and at each position where a cable is branched or reduced in size Yes and to each lamp circuit Yes

If vessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits Yes

Are the fuses of non-oxidisable metal Yes and constructed to fuse at an excess of 100 per cent over the normal current

Are all fuses fitted in easily accessible positions Yes Are the fuses of standard dimensions Yes If wire fuses are used are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit Yes

Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases Yes, porcelain & marble are used

Total number of lights provided for 164 lamps arranged in the following groups:—

A	73	lights each of	32, 16 & 5	candle power requiring a total current of	27.0	Amperes
B	13	lights each of	1,000 & 32	candle power requiring a total current of	17.0	Amperes
C	9	lights each of	1,000 & 32	candle power requiring a total current of	13.0	Amperes
D	27	lights each of	32 & 16	candle power requiring a total current of	15.5	Amperes
E	42	lights each of	16	candle power requiring a total current of	23.0	Amperes
2	Mast head light with	2 lamps each of	32	candle power requiring a total current of	2.24	Amperes
2	Side light with	2 lamps each of	32	candle power requiring a total current of	2.24	Amperes
5	Cargo lights of		128	candle power, whether incandescent or arc lights	incandescent	

If arc lights, what protection is provided against fire, sparks, &c.

Where are the switches controlling the masthead and side lights placed in the chart room

DESCRIPTION OF CABLES.

Main cable carrying	170 Amperes, comprised of	37 wires, each # 14	S.W.G. diameter,	.1820 square inches total sectional area
Branch cables carrying	27 Amperes, comprised of	11 wires, each # 20	S.W.G. diameter,	.0110 square inches total sectional area
Branch cables carrying	17 Amperes, comprised of	15 wires, each # 20	S.W.G. diameter,	.0150 square inches total sectional area
Branch cables carrying	13 Amperes, comprised of	15 wires, each # 20	S.W.G. diameter,	.0150 square inches total sectional area
Branch cables carrying	15.5 Amperes, comprised of	7 wires, each # 20	S.W.G. diameter,	.0070 square inches total sectional area
Branch cables carrying	23 Amperes, comprised of	14 wires, each # 20	S.W.G. diameter,	.0140 square inches total sectional area
Leads to lamps carrying	.5 Amperes, comprised of	1 wires, each # 18	S.W.G. diameter,	.0018 square inches total sectional area
Cargo light cables carrying	4.5 Amperes, comprised of	283 wires, each # 38	S.W.G. diameter,	.0080 square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.


Conductors are doubly insulated with india rubber and vulcanized rubber and tape. Cables are protected against mechanical injury and chemical action by steel armoring or lead covering according to the requirements.

Joints in cables, how made, insulated, and protected Mechanical joints are made throughout and protected with water-tight cast iron boxes

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances Yes Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage Yes

Are there any joints in or branches from the cable leading from dynamo to main switch board none

How are the cables led through the ship, and how protected Cables are led unconcealed and without any additional protection those on cables themselves



Lloyd's Register
Foundation

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible *They are all in accessible places.*

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture *without any additional protection beside those on the cables themselves.*

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat *as before*

What special protection has been provided for the cables near boiler casings *as before*

What special protection has been provided for the cables in engine room *In some parts when necessary the cables are led through iron pipes.*

How are cables carried through beams *Pierced through wood lined through bulkheads, &c. provided with W.T. glands.*

How are cables carried through decks *pierced and led through iron pipes*

Are any cables run through coal bunkers *Yes* or cargo spaces *Yes* or spaces which may be used for carrying cargo, stores, or baggage *Yes*

If so, how are they protected *without any additional protection on the cables themselves.*

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage

If so, how are the lamp fittings and cable terminals specially protected

Where are the main switches and fuses for these lights fitted

If in the spaces, how are they specially protected

Are any switches or fuses fitted in bunkers

Cargo light cables, whether portable or permanently fixed *portable* How fixed *in the W.T. cast iron boxes*

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel

How are the returns from the lamps connected to the hull

Are all the joints with the hull in accessible positions

Is the installation supplied with a voltmeter *Yes*, and with an amperemeter *Yes, two ammeters, fixed on a marble switch-board.*

VESSELS BUILT FOR CARRYING PETROLEUM.

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas

Are any switches, fuses, or joints of cables fitted in the pump room or companion

How are the lamps specially protected in places liable to the accumulation of vapour or gas

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than *600* megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

Electrical Engineers

Date

COMPASSES.

Distance between dynamo or electric motors and standard compass	<i>Dynamo to standard compass</i>	<i>115 ft.</i>
	<i>Motor " " "</i>	<i>110 ft.</i>
Distance between dynamo or electric motors and steering compass	<i>Dynamo " Steering "</i>	<i>105 ft.</i>
	<i>Motor " " "</i>	<i>100 ft.</i>

The nearest cables to the compasses are as follows:—

A cable carrying	<i>5.6</i>	Ampères	<i>6</i>	feet from standard compass	<i>15</i>	feet from steering compass
A cable carrying	<i>13.5</i>	Ampères	<i>17</i>	feet from standard compass	<i>13</i>	feet from steering compass
A cable carrying		Ampères		feet from standard compass		feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power

The maximum deviation due to electric currents, etc., was found to be _____ degrees on _____ course in the case of the standard compass and _____ degrees on _____ course in the case of the steering compass.

KAWASAKI DOCKYARD COMPANY, LTD

Builder's Signature. Date

GENERAL REMARKS.

This installation has been fitted in accordance with the Rules & worked satisfactorily on trial

It is submitted that this vessel is eligible for THE RECORD. ELEC. LIGHT

A. L. Jones

Surveyor to Lloyd's Register of Shipping.

Committee's Minute



© 2020

Lloyd's Register Foundation

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.