

# (LLOYDS REGISTER.)

G. R. 130  
Lloyds.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) \_\_\_\_\_

Official Number.	Name of Ship.	No., Date, and Port of Registry.
116,120	"Elite."	5/1903 Hull

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Screw.	Govan	1902	Mackie & Thomson Govan.

Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	109	Feet.	Tenths.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	108	5	
Rigged ...	Yawl	Main breadth to outside of plank ...	21	6	
Stern ...	Round	Depth in hold from tonnage deck to ceiling at midships ...	10	6	
Build ...	Blancher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	12	16	
Galleries ...	None	Depth from top of beam amidships to top of keel ...	12	4	
Head ...	None	Depth from top of deck at side amidships to bottom of keel	-	66	
Framework and description of vessel ...	Steel	Round of beam ...	-	-	
Number of Bulkheads ...	Four	Length of engine room (if any) ...	27	98	
Number of water ballast tanks, and their capacity in tons ...	One - 22 tons				

### PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ...	250 tons.	Ditto per inch immersion at same depth ...	4 1/2 tons.
--	-----------	--	-------------

### PARTICULARS OF ENGINES (if any).

No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One Set	Engines. Triple Compound Vertical Inverted	British	Engines. 4	Engines. Muir & Houston	Three 11"	22"	48
	Boilers. Number.....One Iron or Steel.....Steel Pressure when loaded 200 lbs		Boilers. 1902	Boilers. Govan.	18" 30"		300 10 knots

### PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	170.74	On account of space required for propelling power	93.56
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Space or spaces between Decks ...		These spaces are the following, viz.:—	
Poop ...		Forecastle & cabins	17.45
Forecastle ...	1.23		
Round House ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, as follows:—	
Other closed-in spaces, if any, as follows:—		Cubic Metres.	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894, if required.	7.73	Master's cabin 1.90	5.90
		Boon's Store 4.00	
Gross Tonnage ...	179.40	508.55	
Deductions, as per Contra ...	116.91	330.86	
Registered Tonnage ...	62.79	177.69	Total Deductions ... 116.91

Name of Master	Certificate of { Service No. Competency No.
----------------	---

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

The Great Northern Steamship Fishing Company Limited of the City & County of Kingston-upon-Hull. } 64 Shares  
William R Nowell of 2 Kensington Gardens, Hesse Road, Hull. }  
— Manager. —

Dated 7 January 1903