

S. S. Seattle continued.

fitted to set upper deck hatches & stays to deck. 2 pillars fitted
aft of N^o 2 hatch. 2 pillars fitted in Engine room. Bulk angle
stiffeners fitted to flat sides of tunnel. Bridge side plating
stake above sheer doubled⁵⁰ for length of bridge & 6' beyond.
Anchors & chains had no certificates, now tested and new
certificates supplied. 1 New Bower Anchor supplied and 15' fms
chain. Stiffeners fitted to floors at wide spaced pillars.
Ruddell lifted & re lashed.

Repairs. - N^o 4 hatch web bent removed & faired.

on Port side fore. - Indents on E. 2. E. 3. G. 4. H. 3 faired in place.

also G. 3. N. 3. Landings faired in place on Starboard side.

The following could not be dealt with at this time and
may be done at Gunnar's convenience.

In way of aft hatch Starboard side 4 plates indented, and 2 on
Port side. Also 1 plate indented at bilge in Eng room Starboard
side, and Port bilge keel bent.

G. D. Dickinson.

When Anchors or Cables are supplied, the particulars are to be reported in the following form:—

ANCHORS.

Number of Certificate.	Anchors.*	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST, PER CERTIFICATE.			WEIGHT REQUIRED BY TABLE 30 or 31.			Description of Anchor.	Makers.	Where and when tested at Superintendent.
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons.	Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.		
25123	1st Bower	60	0	0	Stock			48	7	2	0	60	0	0	Byers Steel	Indult. 16/2/20
	2nd "															
	3rd "															
	Collective Weight.															
	Stream															
	Kedge															

* When a bower anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bower.

CHAIN CABLES.

Number of Certificate.	Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and size per Table 30 or 31.		Description.	Makers of Cables.	When and where tested and Superintendent.
	Length.	Diam.	Statu- tory.	Breaking.	Supplied.	Per Table 30 or 31.	Length.	Diam.			
	Fathoms.	Ins.	Tons.	Tons.	Cwts. qrs. lbs.	Cwts. qrs. lbs.	Fathoms.	Ins.			
12676	15	23/16	86 1/8	120 1/2	36.1.0		15	23/16	Steel		Samdula. 23/1/20 Kapt.
	✓	✓	✓	✓	✓		✓				
Iron Stream Chain } or Steel Wire.... }											

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.



© 2020

Lloyd's Register
Foundation