

2nd March, 1920.

S.S. "SEATTLE"

Newcastle Report No. 72859.

ELECTRIC LIGHTING INSTALLATION

The following work has been done whilst at the Mercantile Dry Docks;

Navigation circuit. Two side lights, two compass lights and flashing lamps and stern lamp are rewired.

The old main cables for midship circuit 7/18 has been taken out and rewired with 7/14. New circuits put in for eight new fans midships and three in the saloon.

Three berths aft rewired.

Stokehold rewired with armoured cable.

New bases fitted in two watertight boxes for cargo clusters, fourteen cargo clusters overhauled, new flexibles and lamp holders fitted.

Gauge lights rewired in engine room armoured cable.

An auxiliary dynamo fitted and 150 A. change over switch fitted.

Dynamo - Makers J.H. Holmes, 110 Amps. 100 volts.

Engine - Makers Robey, Lincoln.

W.T. Badger

Surveyor to Lloyd's Register.



© 2020

Lloyd's Register
Foundation

007139-007149-0213

TUE. 19
FEB. 11 1921