

S.S. "HANSA", No.23567 in R.B.

This vessel, which is of the two-deck type with long combined bridge & poop and forecastle, was built in 1906.

A letter has now been received from the Hamburg Surveyors stating that it is desired to make some modifications in the structure to suit the carriage of motorcars.

It is submitted the Hamburg Surveyors be informed by wire as follows :-

"HANSA hatch coamings inside long poop may be cut as proposed and bolted bulb plate fitted for battening, or three inch coaming and watertight plate hatch covers Stop If tonnage opening on poop be dispensed with and bridge front closed hatchways may be as on lower deck stop Platform deck to have thirtythree inch stringer not connected to shell and tie plates at deck girders Stop Deck girder design approved if of adequate strength."

If the alterations are proceeded with, detailed plans showing the Owners proposals should be submitted for the approval of the Committee.

15. 9. 27. W.S.

Ed. 2 Main  
15/9/27.

*W.S.*  
*C.A.Y.*  
*W.S.*



© 2021

Lloyd's Register  
Foundation