

Do. of
Do. of
Gro
Steel Aux. 3 Masted Ship ^{DAR} "POMORZA" (ex "Colbert")

Cpn. 8282
" 8283

Rule Dimensions - 229.5' x 41' x 23.26'.
Scantling Nos. - 5335 and 14750
Proportions - Length = 9.86 depths to upper deck.

This vessel was built by Messrs. Blohm & Voss, Hamburg,
in 1909 and classed with the Germanischer Lloyd.

She is used as a training ship for boys, an auxiliary motor
engine has been installed and some minor alterations carried out.

With a view to classification with this Society plans and
particulars have been examined in this Office and the Surveyors informed
that provided the usual conditions were complied with and a favourable
report received the vessel could be recommended for the class 100A.

The Copenhagen Surveyors now forward a report giving particulars
of scantlings and further report the vessel placed on a pontoon and the
requirements of the Rules for a vessel not built under survey complied with.

A number of shell plates ^{in hull} were found pitted ^{over} examined but
owing to the excessive thickness no renewals were considered necessary.

The equipment on board is as required by the Rules and has
been tested by Surveyors to this Society.

It is submitted the vessel appears worthy to be classed 100A.1.
with record of survey 6.30 and notation of 2nd S.S. No.3-6.30.

100A1 (Steel)
3 Dks. (U Stl. Teak S)
M.T. D.T.a
BK 9", 6 BH (5 BH to upper dk., 1 BH to 2nd dk.), Cem., Lloyd's A.&C.P.
P 78', F 42'
Date of build 1909
6.30 Cpn.
S.S. Cpn. 2nd No.3-6.30.

The Surveyors should be requested to state the length and capacity
of the midship deep tank and the deep tank aft.

2021
Lloyd's Register
Foundation
007324-007333-0106