

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.—STEAM SHIPS.PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH
TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR
WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS
CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey 1-11-32

Name of Surveyor

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
P.L.M. 26.	ROUEN FRENCH	L	5391	1922-4	+100 A1.
Number in Register Book					
Registered dimensions from Ship's Register.	LENGTH. 400.-	BREADTH. 56.05	DEPTH. 28.45	UNDER DECK TONNAGE. 5119.78	
Length on LOADLINE.	399.50	Frame Depth 11 Rule " 6 1/2 4 1/2	Ceiling +.20 Sheer +.98 4" DROP IN TANK +.30	Peak } INCL. Tanks } DEEP TANK UNDER ENGINES +22 10" FRS. IN NO.1 HOLD -3	
CORRECTED DIMENSIONS.	399.50	55.30	29.93	5138.78	
Co-efficient of fineness.....	.48				
Any modification necessary [Para. 4 (a) to (e)]*	C.D.B.				
Co-efficient as corrected46				
Sheer { Stem..... 126 } at { Sternpost ... 54 }	180 ÷ 2 = 90	Mean			
Sheer at 1/8 of the length from { Stem 66 } { Sternpost 24 3/4 }	93 3/4 ÷ 2 = 46 3/8	Mean			
Gradual mean Sheer	85.23				
Standard mean Sheer [Table, Para. 18]	49.95	Correction			
Difference.....	35.28 ÷ 4 = 8.82				
§ If limited as Para. 18 (f)					-9"
Rise in Sheer { At front of bridge house..... from amidships { At after end of forecastle					
[Para. 18 (e)]					
Fall in Sheer { Para. 18 (d) }	÷ 2 =				
Length uncovered		Correction			
ALLOWANCE FOR DECK ERECTIONS :—					
Freeboard, Table C.....	4'-9 1/2"				
Correction for Length, if required (Para. 12, 13, and 14)	+ 2 1/4				
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 11, 12, 13, and 14) }	4'-11 1/4				
Difference	4'-6 3/4				
Percentage as below.....	2-7				
	31.83				
Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11)					
Allowance for Deck Erections	10"				
Length.	Length allowed.	Height.			
Forecastle..... 40.00	40.00	4-6			
Bridge House 31.50	31.50	4-6			
† Raised Qr. Dk.....					
Poop..... 124.25	124.25	4-6			
Total	198.75				
Length of Ship	399.50				
Corresponding percentage { (Para. 11, 12, 13, or 14) }	31.83				
SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, [redacted], Steel, Deck :—					
Tropical Fresh Water Line above Centre of Disc ... 305.74					1880 1/4
Fresh Water Line " " ... 178. "✓					1575
Tropical Line " " ... 124. "✓					1402
Winter Line " " ... 124. "✓					1453
below " " ... 124. "✓					2004
Winter Freeboard from deck line					
Summer " " " "					
Indian Summer " " " "					
N. A. Winter " " " "					
Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.					
Winter Freeboard	6'-7"				
Summer Freeboard	6'-2"				
Indian Summer Freeboard	5'-9"				
N. A. Winter Freeboard					

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	399.50
Length in Table	392.00
Difference	7.50
Correction for 10ft., Table A.	1.6
Table C.84
× Difference divided by 10	4.40
(if required.) 2.20	
If 1/10ths length covered divide by 2	+ 4 1/2"
	+ 2 1/4"

CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered	49.15
Thickness of usual wood deck, less stringer	3 1/2
	- 1 1/4"

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	53.98
Round of Beam	13 1/2
Normal round.....	13 1/2
Difference	÷ 2 =
Proportion of Deck uncovered (Para. 19)	

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A	4'-11"
Correction for Sheer	- 8 3/4
	4'-2 1/4
Correction for Length	+ 4 1/2
Allowance for Deck Erections	4'-6 3/4
	10
Correction for Round of Beam.....	6'-8 3/4
Correction for fall in Sheer (if any).....	
Correction for Steel Deck (if required)	- 1 1/4
	6'-7
Additions for non-compliance with provisions of { Para. 11 (d) and (e) † }	
Other Corrections (if any)	

Winter Freeboard	6'-7"
Summer Freeboard	6'-2"
Indian Summer Freeboard	5'-9"
N. A. Winter Freeboard	
Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.	
Winter Freeboard from deck line	
Summer " " " "	
Indian Summer " " " "	
N. A. Winter " " " "	

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, [redacted], Steel, Deck :—

Tropical Fresh Water Line above Centre of Disc ... 305.74	✓
Fresh Water Line " " ... 178. "✓	
Tropical Line " " ... 124. "✓	
Winter Line " " ... 124. "✓	
below " " ... 124. "✓	
" " " " ... " "✓	

Tropical Fresh Water Freeboard ...	1880 1/4
Fresh Water " " " " ...	1575
Tropical " " " " ...	1402
Winter " " " " ...	1453
" " " " ...	2004

MARKING FORM
RECEIVED 13 JUN 1933
RECEIVED 13/3/35
RECEIVED 13 FEB 1933