

Lloyd's Register of Shipping.

Ship's Name

"KIYOSUMI MARU"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS.

The tonnage opening hatch at after end of the upper deck has now been removed and the deck inway plated over. The forward bulkhead of the tonnage opening space has also been removed and suitable beams and supports to weather deck fitted in way of alterations.

The freeing ports and scuppers port and starboard from tonnage space have been permanently closed by welded plate.

These ports and the weather deck in way of alterations hose tested and found tight

The new freeboards assigned by the Japanese Government and have been cut in and verified. Please see verification form herewith.

(KOBE. Rpt. 8 No. 10660 dated 18.5.38.).

Noted. LRB

13 JUN 1938