

M-B.40C.



COPY

LLOYD'S REGISTER OF SHIPPING

MEIKAI BUILDING

No. 32, AKASHI MACHI,

KOBE, 30th April 1941.

TELEGRAMS: "REGISTER" KOBE

TELEPHONE: 2530 SANNOMIYA

Messrs. Kawasaki Heavy Industries Ltd.,

K o b e


M/S "KIRISHIMA MARU"

Plan of Crankshaft for Auxiliary Diesel Engine.

Dear Sirs,

In reply to your letter of the 24th instant submitting for approval the above plan in quadruplicate, I have to inform you that with 4.S.C.S.A. heavy oil engines having six cylinders 275 mm. diameter by 420 mm. stroke, span of bearings 328 mm. ~~mean~~ indicated pressure and maximum pressure in the cylinders 6.85 kilog. per square centimeter and 49 kilog. per square centimeter respectively and developing 350 b.h.p. at 375 revolutions per minute, the proposed size of crankshaft, viz., 170 mm. will be approved.

Further, the plan of crankshaft will be approved provided the steel be made at approved Works and the forging be made and tested in accordance with the requirements of the Rules and the crankshaft be made under the usual condition of survey.



© 2020

Lloyd's Register
Foundation

007474-007485-0157 1/2

CONFIRMATION OF LETTER

LLOYD'S REGISTER OF SURVEYORS


1900

1900

One copy of the approved plan is being returned to you herewith.

I am, Dear Sirs,

Yours faithfully,



Senior Surveyor.

The Surveyors,

LONDON

Dear Sir,

I enclose herewith a copy of the plan of the vessel, Kawasaki Heavy Industries Ltd. The plan is a copy of the plan of the vessel, Kawasaki Heavy Industries Ltd. The plan is a copy of the plan of the vessel, Kawasaki Heavy Industries Ltd.

I am, Dear Sir,

Yours faithfully,

A. B. Riddell



© 2020

Lloyd's Register
Foundation