

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Genoa
Date of Survey During Construction
Name of Surveyor M. Constante

Ship's Name. M. V. "GIULIA"
Port of Registry and Nationality. Genoa Italian
Official Number. 3000
Gross Tonnage. 5942.67 Building
Date of Build. Building
Particulars of Classification. + 100 A. 1. Contemplated. Revised Rules

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	<u>407.5</u>	<u>53.93</u>	<u>27.05</u>	<u>4958.05</u>
Length on LOADLINE.	<u>389.42</u>	Frame Depth <u>9.84</u> Ceiling <u>fitted</u> Peak } Incl. Rule " <u>6.0</u> Sheer <u>+ .62</u> Tanks } <u>3.84</u> British Method. <u>7 1/2</u> frames <u>x 2 = .64</u> in lower decks Full breadth <u>58.96</u> — <u>1.25</u> Tons.		
CORRECTED DIMENSIONS.	<u>389.42</u>	<u>58.32</u>	<u>30.10</u>	<u>4956.8</u>

Co-efficient of fineness..... .793
Any modification necessary }
[Para. 4 (a) to (e)]* }
Co-efficient as corrected74

Sheer { Stem..... 108 } 158.5 ÷ 2 = 49.25 Mean
at { Sternpost ... 50.5 }
Sheer at $\frac{1}{2}$ of the length from { Stem 56.5 } 48.5 ÷ 2 = 39.25 Mean
{ Sternpost 22.0 } + .58 = 41.36
Gradual mean Sheer 41.36
Standard mean Sheer [Table, Para. 18] 48.94 Correction
Difference..... 22.42 ÷ 4 = 5.60
§ If limited as Para. 18 (f) -5 1/2

Rise in Sheer { At front of bridge house..... ✓
from amidships {
[Para. 18 (e)] { At after end of forecastle ✓

Fall in Sheer {
Para. 18 (d) } ✓ ÷ 2 = ✓
Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS :—

Freeboard, Table C..... 5.2 3/4
Correction for Length, if required (Para. 12, 13, and 14) + 1/2
5.3 1/4
Freeboard by Table A, corrected for sheer, and for length, }
if required (Para. 12, 13, and 14) } 8.0
Difference 2.8 3/4
Percentage as below..... 36.01%
11.49

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) }

Allowance for Deck Erections - 11 3/4

	Length.	Length allowed.	Height.
Forecastle.....	<u>39.38</u>	<u>39.38</u>	<u>7-6"</u>
Bridge House	<u>137.14</u>	<u>137.14</u>	<u>7-6"</u>
† Raised Qr. Dk.....			
Poop.....	<u>37.43</u>	<u>37.43</u>	<u>7-6"</u>
Total		<u>214.25</u>	<u>5502</u>
Length of Ship	<u>389.42</u>		
Corresponding percentage { (Para. H, 12, 13, or 14) }	<u>36.01%</u>		

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck :—

Fresh Water Line above centre of Disc ...
Indian Summer Line " " " ...
Winter Line below " " " ...
Winter North Atlantic Line " " " ...

16 NOV 1925

* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

Moulded Depth as measured..... 32.0
Addition for Keel below base line for draught record..... inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH

Length of Ship on Loadline..... 389.42
Length in Table 384.00
Difference 5.42
Correction for 10ft., Table A. 1.6 Table C. .8
× Difference divided by 10864 (if required.) .43
If $\frac{1}{10}$ ths length covered divide by 2 + 3/4" + 1/2"

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered5502
Thickness of usual wood deck, less stringer 3/4
3" Sheathing fitted = 3 1/4" assumed mean thickness. 1/4" x .5502 = Say NIL.

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....
Round of Beam
Normal round.....
Difference ÷ 2 =
Proportion of Deck uncovered (Para. 19)

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A 8" 4 3/4
Correction for Sheer - 5 1/2
4" 11 1/4
Correction for Length + 3/4
8" 0
Allowance for Deck Erections - 11 3/4
4" 0 1/4
Correction for Round of Beam..... ✓
Correction for fall in Sheer (if any)..... ✓
Correction for Steel Deck (if required)
Omission of wood sheathing in Bridge - 3 1/4
6.9
Additions for non-compliance with provisions of }
Para. 11 (d) and (e) † }
Other Corrections (if any)

Winter Freeboard 6" 9
Summer Freeboard 6" 3 1/4
Indian Summer Freeboard 5.9 1/2
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood steel deck with side. + 1 3/4

Winter Freeboard from deck line 6" 10 3/4
Summer " " " 6" 5
Indian Summer " " " 5" 11 1/4
N. A. Winter " " "

† State dimensions of freeing port area on back of this form.

The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line, the vessel's draught at time of survey, and also the usual load draft forward and aft should be reported.

RECEIVED

1 JAN 1926