

St Anne


6W.392.

GRAYS, ESSEX.TESTING & EXPERIMENTING WORKS,
99, SOUTHWARK STREET,
LONDON, S.E. 1

6th August, 1943.

RESULTS OF TESTS TO ASCERTAIN THE RESISTANCE TO THRUST OF

three six-inch cubes of Concrete received from Messrs. W. & C. French, Ltd.

TEST NO.	DESCRIPTION	WEIGHT	DIMENSIONS	BASE AREA	CRUSHING STRENGTH		
					TOTAL	PER SQ. INCH	PER SQ. FOOT
ZZZ	Age 28 days. Concrete cube, cast 8/7/43. Marked 1½; BC 1 and with metal tag bearing stamp of Lloyd's Surveyor." 	LBS.	INCHES	SQ. INS.	LBS.	LBS.	TONS
			6.03				
		14.95	5.99 x 5.99	35.9	263,800	7350	473
5203	do.	14.90	5.99 6.01 x 6.01	36.1	263,800	7350	473
5204	do.	14.85	5.99 6.01 x 5.98	35.9	220,700	6150	395
					Mean	6880	443

Messrs. Sir E.O. Williams & Partners,
14, Warren Fields, Valencia Road, Stanmore, Middlesex.David Kirkaldy & Son
© 2020
Lloyd's Register
Foundation
007626-007638 0088