

## Lloyd's Register of Shipping.

Ship's Name "PLETTENBERG"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS TO SHIPS STRUCTURE.

A new additional bunker hatch was fitted on fore part of Bridge deck for cross bunker 6' x 2' x 18' coaming with wood hatch covers, 3 tarpaulins, and locking bar, doubling plate fitted under this hatch to maintain strength of deck.

Firemens house built of steel, partly on poop and partly on deck tank, (deck tanks are fitted between all hatches.)

Wash house Starboard side, and W.C. Port side of steel, built at front poop on quarter deck. Deck and ships side pierced, for soil pipe, storm valve of approved type was fitted.

Closing Appliances :- Forecastle hinged wood door S. and riveted plate - Bridge for and 2 bolted steel plates. Bridges after and no openings, poop no opening - Hinged steel doors to accommodation aft.

*Extract from Port Natal Rpt 8. No. 3778 dated*

*13/8/42*

*Noted*

*[Signature]*  
*11/10/42*