

COPY.

M.V. "KATSURAGI MARU".


14th November, 1931.

It is submitted Mr. Cox's attention be called to the registered depth given on the First Entry Report of this vessel, viz 40.06', as it would appear that this should be 30.06 feet.

This vessel has a tonnage opening in the shelter deck and therefore the space between the shelter and second decks will in a large measure be exempted from tonnage measurement. In these circumstances the second deck is the uppermost continuous deck within the meaning of the tonnage regulations, and therefore it is considered that the official registered depth should be measured to this deck.

Similar remarks will apply in the case of the "KIRISHIMA MARU", No. 25646 in the Register Book.

Mr. Kobe
14/11/31
See fwd rpt.



14. 11. 31.



© 2020

Lloyd's Register
Foundation

007658-007667-0258

FK, 8 B.H. (Coll B.H. to Shelter D*) Lloyd's ACP