

Lloyd's Register of Shipping,

(MEIKAI BUILDING)

32, AKASHI-MACHI,

Hakodate

KOBE,--

10th July, 1930.

Cert. No. 467 2

This is to Certify that at the request

of Messrs. Nippon Seikosho Co., Ltd., Yokohama,

the Open Hearth Steel Forgings or Castings named below ^{was}~~were~~ examined and

tested at their works on the 20th 21st February, 4th June and 10th July,

and found to be as far as could be ascertained, sound and free from defect.

Five (5) rudder arm, in partly finished machined condition.

Drop tests : Dropped from a height of 12 feet on to hard ground

then suspended and hammered without indication of defect

Test Mark	Tenacity Tons/sq in	Elongation % in 2"	Bend 120 °
401683 2	33.8	29.5	Satisfactory
401661 4	31.5	29.0	--"--
401662 2	31.8	27.5	--"--
401688 3	33.9	29.1	--"--
401688 5	33.5	33.0	--"--

These rudder arms

intended for

S. No. 473-474

Mitsubishi Nagasaki Zosensho

and ^{has}~~have~~ been stamped as follows:-

Fee Yen

45:00.

401688 2
L.R. Lloyd's No. 686
Z.S. 9-7-1930

401661 4
L.R. Lloyd's No. 687
Z.S. 9-7-1930

Expenses "

25:00.

401662 2
L.R. Lloyd's No. 688
Z.S. 9-7-1930

401688 3
L.R. Lloyd's No. 689
Z.S. 9-7-1930

401688 5

Lloyd's No. 690
Z.S. 9-7-1930

Assistant

Surveyor to Lloyd's Register.

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :--
While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be
understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy
of report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the
Society, or for any error of judgment, default, or negligence of the Surveyors, other Officers or Agents of the Society."

Lloyd's Register
Foundation

007679-007687-0196

