

ADVICE NOTE.

CHESTERFIELD,

Advice No. 1265.

Messrs. Mitsubishi Shoji Kaisha, Ltd

6th March 1930.

Cory Buildings, 117, Fenchurch S



TELEPHONE No. 2161 (3 LINES), CHESTERFIELD

TELEGRAMS: "TUBES, CHESTERFIELD"


London. E.C.3.

From

THE CHESTERFIELD TUBE CO. LTD.

Your Order No. N. 1897.

Our Order No. 1969/29.

Quantity.	Description.	Length.		Weight.				Marks.	Truck No.
		Feet.	Inches.	Tons.	cwts.	qrs.	lbs.		
	COLD DRAWN HIGH PRESSURE AIR BOTTLES. For Injection Air. British Lloyds Inspection. 2 - 332 m/m o/d x 16 mm thick x 2320 m/m. Overall. FOR NAGASAKI SHIP No. 474. Nos.- 186664-5. The base formed integral with the walls in the process of forging, 48 mm, machined flat externally, bored 60.5 m/m after hydraulic test, and recessed diameter for 4 m/m deep, and drilled and tapped 6 - 3/4" Whitworth Holes on 120 mm Circle diameter. The opposite end necked down and complete with Mild Steel 10 m/m diameter x 52 m/m thick, screwed on and tapped six holes 1 1/4" Whitworth. and screwed vanishing thread to our drawing. Cylinders painted black. Mark.-  protected with timber. Weight.-								
		</							



RW Fawcett

We have this day consigned in good order and condition the above mentioned Goods per

by, Carriage

paid. f.o.b.

Packed in

loose.

cases

L. & N.E.R.

bundles.

Birkenhead Dock, Birkenhead, for shipment per ss "DAKAR MARU". Order of.-

Messrs. Thos. Robinson & Son, Ltd., 25, Water Street, Liverpool.

We do not hold ourselves responsible for any Shortage in and/or Damaged Goods unless the Delivery Note is so endorsed before being signed, in event please at once return Advice Note to us with explanatory Memorandum.

THE CHESTERFIELD TUBE CO. LTD

007679-007687-0208

1930