

COPY.

Lloyd's Register of Shipping.



Port of Düsseldorf.

9th April 1930.

Order: P.946.

This is to Certify that

Friedrich Kohlsaat

the undersigned Surveyor to this Society did at the request of Messrs. Press- & Walzwerk A.G. of Düsseldorf-Reisholz test and inspect on the 6th November, 27th November and 4th December 1929 at their work the undermentioned seamless Siemens-Martin Steel air receivers, ordered by Messrs. Mitsubishi Shoji Kaisha Ltd. of Nagasaki and destined for the vessel No.474.

Specification.

No. of rec.	Outs. diam.	Thickness of shell	Length of receivers
5	840 mm	32,5 mm	5680 mm

Results of tests.

Sample No.	Tensile ten. in kg.p.sq.mm.	Elongation in 200 mm
28	44,6	24,5%
29	47,4	25,5%
34	47,8	25,5%
36	44,9	24,0%
37	48,1	23,5%

Band tests good.

Hydraulic test: 2130 lbs.p.sq.inch.
Working pressure not to exceed! 1065 lbs.p.sq.inch.
For identification the receivers have been stamped as follows:

.....
No.787 & 788	No.787	No.790 & 792
LLOYDS TEST	LLOYDS TEST	LLOYDS TEST
2130 lbs.	2130 lbs.	2130 lbs.
W.P.1065 lbs.	W.P.1065 lbs.	W.P.1065 lbs.
F.K.C.11.29	F.K.27.11.29	F.K.4.12.29
.....

F. Kohlsaat
Surveyor to Lloyd's Register

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for accuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."

APR 30 1930