

PLAN No. 2760
FOR ENCLOSURE TO
Messrs Lloyds Surveyors
Hull FROM
COCHRANE & SONS, LTD.
SHIPBUILDERS, SELBY.
DATE 18/4/13. RK

25. 4. 13

TO CLASS 100.A.1 STEAM TRAWLER
DIMENSIONS 117'-0" B.P. x 22'-0" EXT. x 12'-9" MLD.
SCALE 1/2 INCH.

NUMERALS.

PROPORTIONS.

EQUIPMENT.

owners consent
bottle wine

RIVETING

- ✓ BUTTS OF SHELL PLATING OVERLAPPED & DOUBLE
- ✓ RIVETED EXCEPT GARBOARD AND SHEERSTRAKE
- ✓ WHICH ARE TO BE STRAPPED & DOUBLE RIVETED
- ✓ ALL SHELL SEAMS EXCEPT BULWARKS TO BE
- ✓ DOUBLE RIVETED. BULWARKS SINGLE RIVETED.

Jul
25.4.13

Cochrane & Sons. Ltd.

N. 575.

Midship Section

Dimensions 117.0 x 21.87 x 12.75

1/2 Piece Lead

Hull Report No. 26732

SHIPBUILDERS' SECTY
COCHRANE & SONS, LTD.
FROM
Messrs Lloyd's Bureau of
Hull
DATE 18/4/13.



© 2020

Lloyd's Register
Foundation