

# COPY.

T.S.M.S. "MAULY".  
-----

Extract from Tri. Rpt. No. 9166, dated 2.5.31,  
-----

....."Alterations. Now done. At the after bridge  
"end bulkhead, 2 hinged W.T. Steel doors have been replaced  
"by temporary closing appliances consisting of hinged W.T.  
" Doors fitted on ~~portable~~ frames secured to the bulkhead  
"by bolts hooked inside and passing through the frames but  
"not through the bulkhead.

"In the forecastle end bulkhead an opening has  
"been made closed by a strong portable steel plate secured  
"to the bulkhead by bolts hooked inside and passing through  
the portable plate but not through the bulkhead.

"The scuppers in way of bridge and forecastle  
"spaces with the temporary closing appliances at the after  
"ends as above, have been fitted for draining overboard  
"and provided with storm valves as required".....



© 2020

Lloyd's Register  
Foundation

007722-007730-0302