

TILL CO. (ENGLAND) LTD.

MING, K.C., M.P.
IAMS, F.A.L.P.A., F.V.A.
(British)
(Indian)

78, NEW OXFORD STREET, LONDON, W.C.1

Telephone: MUSEum 9351-2

Cables: TILLCO, LONDON

APPROVED AGENTS BY (I.A.T.A.) INTERNATIONAL AIR TRANSPORT ASSOCIATION

HL/DS

LONDON, 13th. May, 1948.

The Secretary,
Lloyd's Register of Shipping,
71, Fenchurch St.,
E.C.3.

RECEIVED

14 MAY 1948

19

Dear Sir,

A/c 814

re; s.s. "SINAI"

I have to-day received a letter from Major S.H. Hambling with regard to the queries you raised on the 4th. inst., regarding the above vessel; the following are the answers:-

- (1) Where there are differences I would say that the profile is correct.
- (2) The thickness of the forecastle side plating is 15/40".
- (3) If the owners decide against converting this vessel to carry passengers then cargo can be carried in the tween decks and no trunk will be necessary. Any pillars removed by the Admiralty to suit their requirements will if necessity require to be refitted.
- (4) The Poop side plating referred to is a deck structure and the plating arranged vertically with the edges flanged to eliminate stiffeners.
- (5) Throughout the profile the Admiralty system of thicknesses has been used, i.e. 40 lbs. corresponds to 1" plating, 10 lbs. plating represents $\frac{1}{4}$ " and so on.
- (6) The midship section was prepared from ancient documents and the original nomenclature adhered to.

STEAMSHIP, AIR & RAILWAY TICKETS - FORWARDING - COMMISSION AGENTS - SHIPPING AGENTS - INVESTMENTS - INSURANCE

007806 - 007816 - 0165

The Surveyors,
Per :-

Lloyd's Register
Foundation

RECEIVED
28 APR 1948

Sir,

Mr. L
discu
ificat

Sir,

Mr. L
discu
icate

The v
pool
ed i
"LUC
nior,

We en
ation

Germa
ers i
ers
fit

Mr. L
e in
nec
by y
d ca
uss
d.

ne q
we s
the

eto

TILL CO. (ENGLAND) LTD.

18 NEW OXFORD STREET, LONDON, W.C.2

THE LLOYD'S REGISTER OF SHIPS
LONDON, ENGLAND

THE LLOYD'S REGISTER OF SHIPS
LONDON, ENGLAND

-2-

I shall be glad if you can now proceed with matter.

Yours faithfully,
TILL CO. (ENGLAND) LTD.

H. Landy

H. Landy.

RECEIVED
14 MAY 1948

Referred to the Chief Ship Surveyor.

AKB



© 2020

Lloyd's Register
Foundation