

ADVICE NOTE.

CHESTERFIELD,

Advice No. 5257.

Messrs. Mitsubishi Shoji Kaisha, Ltd

30th December 1929.

Cory Buildings, 117, Fenchurch S



TELEPHONE No. 2161 (3 LINES), CHESTERFIELD

TELEGRAMS: "TUBES, CHESTERFIELD"

London. E.C.3.

From **THE CHESTERFIELD TUBE CO. LTD.**

Your Order No. N. 1897.

Our Order No. 1969/29.

Nos.	Quantity.	Description.	Length.		Weight.				Marks.	Truck No.
			Feet.	Inches	Tons.	cwts.	qrs.	lbs.		
		COLD DRAWN HIGH PRESSURE AIR BOTTLES. Lloyds Insp. - For Injection Air.								
	2 -	332 mm o/d x 16 mm thick x 2320 mm. Overall.							13 2 14.	
		Cylinders Nos.- 189663. 189666.								
		The base formed integral with the walls in the process of forging, 48 mm thick, machined flat externally, bored 60.5 m/m after hydraulic test, and recessed 4 m/m for 4 m/m deep, and drilled and tapped 6 - 3/4" Whitworth Holes on 120 m/m P.C. The opposite end necked down and complete with Mild Steel Flange 310 m/m diameter x 16 mm thick screwed on and tapped 6 holes 1 1/4" Whitworth Thread. Necked end screwed with 1/2" thread to our drawing No. 2762 C/1. Ends painted black.								
		SHIP 473. 18 9 7 NAGASAKI. Nos. 1 & 2.							RW Hawcett 2/1/30	
		Flanges fitted with timber weight.-							2 lbs.	

We have this day consigned in good order and condition the above mentioned Goods per

Railway, Carriage paid. f.o.b. Packed in loose cases L.N.S.R. bundles.

To Docks, Birkenhead for shipment per ss "LIMA MARU". Order of.- Messrs. Thos.

Robinson & Son, 25, Water Street, Liverpool.

We do not hold ourselves responsible for any Shortage in and/or Damaged Goods unless the Delivery Note is so endorsed before being signed, In this event please at once return Advice Note to us with explanatory Memorandum.

THE CHESTERFIELD TUBE CO. LTD

LB 10 1930

publicat
of the S

007825-007833-0166