

S.S."PORT CURTIS".

Liverpool report No.80716.

Extract from letter received from the Belfast Surveyors:-

"Please note that to complete the L.M.C. 5-20 survey, a perforated iron cover plate is to be fitted over the manhole to the "well" in the Engine Room, adjoining the after bulkhead, at the Port Corner, into which the Bilge Injection Pipe, and two water circulating drain pipes project.

"This cover plate should be studded and fitted with distance pieces in order to leave clear opening between it and the tank top of about 1".

"The relieving tackle to the steering gear requires to be adjusted and again tried in place."

The survey on Refrigerating Machinery and Appliances has been completed here and the report will be forwarded on the 28th instant.



© 2020

Lloyd's Register  
Foundation

007825-007833-0227