

s/s Port Curtis.

Bel Rpt 8336
Lw " 80716.

This vessel is fitted with two steam turbines geared to one screw shaft, and the machinery is now satisfactorily reported upon. Having regard to the designed high load on the gear teeth, it was considered advisable to limit the power transmitted during the voyage by locking off nine of the twenty turbine nozzles until a new set of gearing is ready to replace the present set. The survey was completed at Liverpool. It is submitted that

this vessel is eligible for
THE RECORD. + LMC 5.20. F.D.

2 Steam Turbines geared to 1 Screw shaft.



© 2020

Lloyd's Register
Foundation

007825-007833-0228