

18 AUG 1947

Steam Trawler "WINSTON SPENCER CHURCHILL"

Antwerp Rpt. No. 24305 dated 9.5.47.

The Rpt. 13 on the Electrical Installation has been examined and indicates that the generator fitted is a 20kW machine but the generator main cables are as approved for the 15kW machine shown on the plan approved and insufficient for the current of the generator ~~fitted~~ *insured*. Further, a heating circuit is reported as having been installed although no such circuit is indicated on the approved plan, and the stated current is in excess of the rating of the cable reported.

IT IS SUBMITTED the Surveyors be informed that the current carrying capacity of the generator main cables reported, whilst suitable for the 15kW generator shown on the approved plan is inadequate for the 20kW machine reported as having been fitted and will require to be replaced by 19/.083V.C.L.C. cables to comply with Rule requirements and that the feeds to the heating circuit are also inadequate for the current reported and will require to be increased to 7/.044V.C.L.C. X

[Signature]

15.8.47.

lsaw



© 2021

Lloyd's Register
Foundation

007888-007894-0048