

3. Suitable provision being made for the use of the ship which should be available for use in any part of the regular working of the ship which might have to be used by the crew in the regular working of the ship.

5m.5.32.

FREEBOARD REPORT on the "DEVA".


It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval.

Subject to:-

1. The wood fore and afters being steel shod at all bearing surfaces as required by the Convention.
2. Efficient closing appliances being provided for all air pipes
3. Suitable provision being made for rigging lifelines which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.

For timber deck cargoes.

4. The surveyor being satisfied that the bulwark stays are efficiently riveted to the stringer plate, and that the efficiency of the bulwarks is not impaired by attaching the lashings for timber to the shakles in the bulwark stays.



© 2020

Lloyd's Register
Foundation

007909-007918-0224

Certificate written

noted for posting

7
6
3