

Lloyd's Register of Shipping.

Ship's Name *"EMPIRE SCOUT"*Official No. *167395*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in *✓*

Extra crew accommodation has now been arranged at fore end of bridge space. To provide access to this space a steel companionway has been constructed on port side of bridge deck at fore end of No 2 hatch.

The opening in deck is 4'-0" long & 2'-3" wide & fore & afters have been arranged to take the beam that has been cut.

The companionway is 6'-4" high with curved top of $\frac{5}{8}$ " plating & coaming 18" high & $\frac{3}{8}$ " thick. The door is of steel, hinged & made watertight with clips & packing, operated from both sides. A copy of this report has been supplied to vessel.

Alt Hunter 3/10/40

Noted L.R.

67 OCT 1940