

# Lloyd's Register of Shipping.

Ship's Name CHARTEREDOfficial No. 146145

*Memorandum of alterations reported since ship was surveyed for assignment of Load Lines*  
in MARCH, 1932.


Flush scuttle for access to forward hold now dispensed with.

4'0" x 1'9" steel access hatch to Nos. 1 and 2 holds fitted

on top of hatch trunk port side. Coamings 18" x  $\frac{3}{8}$ " thick, top

plate 7/16" thick, secured by hinged eyebolts and nuts. Unlaced

hemp joint in channel fitted on top of coaming. (Nwc. Sept. 1937).



© 2020

Lloyd's Register  
Foundation

007430-007437-0208

Trunk, Forward ...  
Exposed Machinery Casings on Deck  
board Raised Quarter Decks ...

.32

3x3x34

31" - 34"

Blacked at top

6.4'6" x 2'3"  
1.5'6" x 2'3"

18"

7'-0"