

COPY.

Certificate No. 13663

IVERS.

Lloyd's Register of Shipping.

GOTHENBURG FIRST ENTRY REPORT No 18555

Port GOTHENBURG

5th October, 1951.

This is to Certify that

O. Scotting,

the undersigned Surveyor to this Society did at the request of
Messrs. Nydqvist & Holm AB., Trollhättan.

attend their Works on the 10 - 21/9 1951. for the purpose of
inspecting and testing Two 400 lit. E.W. air receiver,
made to the order of Gotlands Slipstensbolag, Burgsvik.
and intended for m.s. "VALE"

The material has ~~been~~ tested as required by the rules, and the
cantlings of the air receiver are in accordance with the approved plan.

The air receiver was, in the presence of the undersigned, tested
by hydraulic pressure to 42 kgs. per square cm. and
found satisfactory.

PARTICULARS.

RECEIVER NUMBER.	LENGTH. MM.	INTERNAL DIAMETER MM.	THICKNESS. MM.	TENSILE STRENGTH. KG/MM.2	ELONGATION. 0/10 IN 200 MM.	BENDS. DEGREES.
6-5117	2300	480	16	41.0 - 46.7	28.5-22.5	180°
Particulars of E.W. tests Class II a.						
			16	41.0 - 41.8	-	180°
Nick bend test good.						

Identification Mark:—

No. 2412 - 2413
LLOYD'S TEST.
42 Kgs.
W.P. 25 Kgs.
OS 21.9.51

[Signature]

Surveyor to Lloyd's Register.

Fee Kr 55:00

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly
is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances
be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any
Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its
or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.

007967-007976-0096