

FITTINGS TO FW TANK UNDER CABIN FLOOR		
ELBOWS	2 OFF	2 1/2" PAINTED W/ BLACK PAINT
FILLING CAPS & CHAINS	1 OFF	2 1/2" G.W. SCREWED CAP & CHAIN
SCREWING PIPE CAPS	1 "	1 1/2" G.W. SCREWING PIPE SCREW DECK CAPS.
		F.77
		F.90



DUDGE PIPES TO BE GALVANIZED W/  
WITH FLANGED JOINTS  
STOUND BOXES :- OF GALVANIZED W/ TO BUILDERS PATTERN  
STOUND PIPES :- OF PAINTED MOUNTAIN IRON  
STEEL STRIKING PLATE TO BE BEDDED IN CEMENT ON  
SHELL PLATING UNDERNATH EACH STOUND PIPE  
AIR PIPES :- CAST IRON OR PAINTED W/ GOOSE NECKS HAVING SHOWN  
WHERE AIR PIPES ARE COMBINED WITH FILLING PIPES A GUN METAL  
SCREWED FILLING PLUG IS TO BE FITTED  
AIR PIPES TO BE FITTED AS HIGH UP UNDER BULKHEADS  
AS PRACTICABLE  
I - 1 1/4 G.M. DOCKING PLUG TO BE FITTED IN EACH  
COMPARTMENT AS PER LIST.

- 1 - FORE PEAK TANK
- 1 - STORE
- 1 - BOILER SPACE
- 2 - BOILER FEED TANK (PORT & STARBOARD)
- 1 - ENGINE ROOM
- 1 - UNDER CREW SPACE

8 OFF  
DOUBLING PAD TO BE WELDED INSIDE SHELL  
PLATING IN WAY OF EACH PLUG

THE REQUIREMENTS OF MINISTRY OF SHIPPING  
NOTICE M 181, SECTIONS 7 & 8, TO BE COMPLIED  
WITH SO FAR AS THEY ARE APPLICABLE.

THE REMAINING REQUIREMENTS OF SECTION 34  
OF THE RULES 1939-40 TO BE COMPLIED WITH  
SO FAR AS THEY ARE PRACTICABLE

SO FAR AS THEY ARE PRACTICABLE

11/1 2204  
385

JAP 23/9/41

Noted  
11/1  
24/9/41

This Drawing and the Information it contains are the Property of RICHARD

This Drawing and the Information it contains are the Property of RICHARD DUNSTON LTD.  
It is not to be Traced, Copied or Published without their Written Consent, nor is the  
Information thereon to be misused in any way.

YARD No. T.358/61.	DRG. No. 2645
--------------------	---------------

TITLE:- PUMPING PLAN.

SCALE :-  $\frac{1}{4}"$  TO ONE FOOT

REF	BORE	PURPOSE
1	5"	MAIN INJECTION
2	3 1/2"	BILGE INJECTION
3	2 1/2"	BILGE MAIN
4	2 1/8"	G.S. PUMP SECTION FROM BILGE MAIN
5	2 1/2"	SPECIAL BILGE
6	2 1/2"	ENG. BILGE PUMP SECTION
7	2"	BILGE SUCTION FROM DECK COMPARTMENT
8	2"	" " " " E.R. HAT
9	2"	" " " " TUNNEL HAT
10	2"	" " " " STOREHOOD
11	2"	" " " " F.O.B. COMPARTMENT
12	2"	SUCTION FROM DECK BEAK
13	2"	FOSS
14	2 1/2"	G.S. PUMP SECTION FROM PENNS.
15	2 1/2"	" " " " SEA
16	2"	DRAINAGE TO PENNS.
17	2"	" " " " DECK
18	2"	" " " " OVERBOARD
19	2"	AUX FEED PUMP SUCTON FROM SEA
20	"	" " " " HOTWELL
21	"	" " " " DISTANCE
22	"	" " " " STAINLESS STEEL

**RICHARD DUNSTON LTD.**  
**SHIPBUILDERS,**  
**THORNE, YORKSHIRE**

DRAWN BY <i>L.L.</i>		DATE <i>16-9-1940</i>
TRACED BY		DATE
CHECKED BY <i>W.L.</i>		DATE <i>16-9-1940</i>
REVISIONS		
No.	DATE	PARTICULARS
<i>1</i>	<i>14-9-40</i>	<i>APPROVED BY LLOYD.</i>
<i>2</i>	<i>1-10-40</i>	<i>POSITION OF F.W. TANK ALTERED</i>
<i>3</i>	<i>9-9-40</i>	<i>FORE-BET PEAKS MADE BY PEAKS.</i>

This Drawing and the Information it contains are the Property of RICHARD DUNSTON LTD.  
It is not to be Traced, Copied or Published without their Written Consent, nor is the  
Information thereon to be misused in any way.

YARD No. T.358/61.	DRG. No. 2645
--------------------	---------------

TITLE:- PUMPING PLAN.

SCALE :-  $\frac{1}{4}$ " TO ONE FOOT

007988-007997-054



R. Dunston

358/61

LONDON COPY.

007988-007997-0054

S/V TARPAN

LOS

M/M. 7992

Dunston Yd. Nos 358/61

⑩ Pumping Plan 007988-007997-0054



© 2020

Lloyd's Register  
Foundation