

DISCLOSED

SECTION.

No. 516

20 JAN 1942

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME KANLAON II Rpt. L.A. No. 7970

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

The class is subject to 15 fathoms of chain cable being supplied.

The Surveyor appointed by Lloyd's Agents at ILOILO reports (10.41) the vessel placed on a slipway, bottom coated, repairs or renewals to shell plating, decks, steering arrangements and minor repairs effected.

A length of chain cable has been supplied, but the marking quoted does not furnish any evidence as to whether this length has been tested.

It is stated the starboard chain cable has several worn lengths, the smallest of which is 15/16". The cable as a whole is 1" diameter (originally supplied 195 fathoms of 1.3/16" - Rule limit 1.1/16").

The diameter as reported is below the limit, and accordingly the cable requires to be renewed. It is not clear whether all the chain cable is worn below the limit or whether the chain cable on starboard side only is so worn, and under the present circumstances it is not possible to obtain a reply to any enquiry. In either case the deficiency is such as to warrant the deletion of the figure "1", which can be restored as part of the class when the equipment has been placed in order.

It is accordingly submitted the figure "1" be deleted, and that the vessel appears otherwise worthy to remain as classed with record of survey 10.41, subject to a length of chain cable being verified.

100A-)
For Philippine)
Coasting Service) Subject, etc.
10.41 Ilo)

15-1-42



© 2020

Lloyd's Register
Foundation