

*D 120 777*  
S. S. "WAR PICTURE" (Messrs. Furness Shipbuilding Co's  
No. 16). Standard "N1." type.

A letter has been received from the  
Middlesbrough Surveyors regarding the equipment, supplied  
from stock to this vessel, by the Ministry of Shipping.


The Surveyor states that the Ministry of  
Shipping and the Builders are both anxious that the  
anchors as proposed will be approved by the Committee  
for the figure "1"

The equipment as required by the Rules, and  
as supplied to the vessel is as set forth below:-

	<u>RULE.</u>	<u>SUPPLIED BY MINISTRY OF SHIPPING.</u>
	c. q. lbs.	c. q. lbs.
Bower anchor ex stock	68 " 0 " 0	68. 3. 22
do	68 " 0 " 0	65. 1. 3
do	58 " 2 " 0	59. 3. 14
Total weight of bower anchors	194 " 2 " 0	194. 0. 11
Stream anchor ex stock	19 " 0 " 0	19. 0. 0
do stock	4 " 3 " 0	4. 3. 21
Kedge anchor ex stock	8 " 0 " 0	8. 1. 8
do stock	2 " 0 " 0	2. 0. 14
Total weight of all anchors=	228 " 1 " 0	228. 1. 26
10 fathoms 2 5/16 stud chain cable.	720 " 3 " 4	725. 1. 7

From the above it will be observed that the  
collective weight of the Bower anchors is 1qr. 17lbs. below the  
Rule requirements. In view however of the total weight of all the  
anchors being 26 lbs, and of the stud chain cable being 4cwt.2qrs.3lbs.  
above the Rule requirements, the equipment of anchors and chains  
is submitted for the favourable consideration of the Committee for the  
figure 1.

FRI. AUG 6 1920



Lloyd's Register  
Foundation  
6.8.20.

007998-008007-0125

*Submission*  
*Approved*  
*Ln 31/7+4/8/20*  
*and 6/8/20*  
*3 test Certs*