

Lloyd's Register of Shipping.

Ship's Name S.S. "VALBORG"

Official No. 167454

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in ✓

Accommodation now fitted in Poop.

Openings :- Tonnage openings in Poop bulkhead now plated over and riveted. |

Particulars of Companionways :- Steel companionway to Poop accommodation utilising part of existing hatchway. Remainder of hatch plated over. Companion 3'-0" x 2'-6" x 6'-3" high, opening 4'-7" x 2'-0" with stout wood door. Sill 15" above deck.

Hatch on upper deck inside Poop fastened down and wood covers caulked and payed.

Ventilators :- Poop deck 4 - 6" dia. Cowl vents } coamings 30" high.
2 - 6" dia. Mushroom vents }

Wood plugs and covers supplied for all vents.

Sidelights :- 3 @ 9" dia. starboard, 2 @ 9" port.

1 - 16" escape scuttle on Poop front starboard.

Scuppers + Sanitary discharge pipes :- Drainage from washplace etc. led above deck through Poop front bulkhead with screw plug.

Sanitary discharges led overboard above freeboard deck with storm valves on shell.

Noted
W. K.

J. J. Jamieson + R. H. Welch
Greenock
12/5/43

17 MAY 1943