

Lloyd's Register of Shipping.

17 JUN 1942

Ship's Name s.s. "SOBORG".

Official No. 171315

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

BARRY - June 1942.

Bridge After Bulkhead.

Opening (s.s.) partly plated over and framed teak door $1\frac{7}{8}$ " thick with bolted steel plate on outside now fitted, giving access to additional accommodation provided for gunners; door operated from both sides. Size of opening 23" x 4'4", sill 22".
2 Additional $10\frac{1}{2}$ " side scuttles provided at shell, fitted with hinged deadlights.

Bridge Deck.

One additional 6" diameter mushroom ventilator with screw down top; coaming .25".

Forward Well.

Additional freeing port 3'9" x 9" provided each side.

After Well.

Additional freeing port 3'9" x 6" provided each side.

A copy of the above has been placed on board the vessel.

Noted
S. J. B.
17/6/42

J. G. Richardson.
16/6/42

