

2-MAR-1949

LLOYD'S REGISTER OF SHIPPING

PORT

TRINIDAD, B.W.I.

17th January, 1949.

THIS IS TO CERTIFY that

J. C. SUBITT


the undersigned Surveyor to this Society did at the request of the Master of the H.M. "FLAGLER" of PANAMA 8200 tons gross and on instructions from Messrs. GEO. F. HUGGINS & CO. LTD. (Lloyd's Agents) on 10th January, 1949 and subsequent dates proceed on board the above vessel whilst afloat in this Harbour, on account of reported leaks in the centre boiler.

I was informed that at approx 1855 hours on 6th January, 1949, leaks developed in centre boiler starboard smokebox.

On examination, it was found that the tubes in the starboard smokebox had been leaking, as were twelve tubes in centre smokebox. The tubes plates were cleaned and no evidence of cracks found in same. The back end of centre furnace was examined when four tubes were found to be leaking slightly, also short section of seam.

It was recommended that leaky tubes be expanded and seam caulked as required.

On completion of above repairs an hydraulic test of one hundred and eighty pounds pressure was applied to boiler and found satisfactory. Boiler later examined under steam and found in order.


Surveyor to Lloyd's Register of Shipping.



© 2020

Lloyd's Register
Foundation

005065-005078-0007