

M.V. "LAVORO".

No. in R.B. 79299.

Classification

It is stated in Baltimore Reports that the entire aft quarters and machinery spaces were re-wired; existing fixtures being used in the machinery spaces, and a First Entry Rpt. has been submitted.

The installation would appear to be in order and such as could be classed with the exception of alternative lighting in the machinery spaces and also that no information is given as to the currents in the circuits whereby the size of the cables can be checked.

IT IS SUBMITTED the Baltimore Surveyors be asked for further information as follows:-

1) It is a requirement of the Rules, Section 4, Clause 9 that in the machinery spaces the lamps be grouped on two circuits so that in the event of one fuse blowing these spaces are not left in darkness.

Their reply in First Entry Rpt. No. 8158 on the question of alternative lighting is "none" and their further comments ~~on this~~ non-compliance with the Rule Requirements are awaited.

2) No information is given in the Rpt. as to the current of the various lighting and motor circuits and this information should be supplied in order that the size of the cables may be checked. It is a requirement of the Rules that plans of the electrical installation should be supplied and as this installation was entirely re-wired at Baltimore there should be no difficulty in supplying these plans.

L. N.Y.K. 27.6.45



© 2020

Lloyd's Register
19.6.45.
Foundation

008122-008128-0165