

ed by Chief Engineer Surveyor.....

Received from Chief Engineer Surveyor.....

SEL'S NAME "TAIAROA" REPORT Auk. No. 4447

Remarks of the Chief Engineer Surveyor are desired on this case for the consideration of the Classing Committee.

(The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement.—Extract from Sub-Committee's Report, 24/5/92.)

of Survey ~~REPORTS TO ENGINEERS AND BOILERS BUT TO DAMAGE THROUGH~~

This vessel and its machinery were built under the supervision of the New Zealand Government Authorities. No evidence that the boiler was built under this Society's survey can be found, but it appears to be a duplicate of these for the "MALDANNA" and "MOONA".

Classification with this Society is now desired.

First Entry Reports have been examined and the details are similar to the above-mentioned vessels which were previously accepted.

The vessel has been examined in dry dock and the requirements of LMC and Screw Shaft Surveys carried out.

The boiler has now been converted to burn oil, in accordance with Rule requirements. It is, however, not clear whether the fire extinguishing apparatus conforms to the Society's present practice.

IT IS SUBMITTED that this vessel is eligible for the Record LMC 12.46,

S (CL) 11.46,

"Fitted for oil fuel 12.46, F.P. above 150° F".

The Auckland Surveyor should be informed that, in previous vessels of this type, such as "MOONA" and "MALDANNA", it was found that the boiler water gauges were connected to the boiler by valves. The Society's Rules require that cocks should be used and the Surveyor's comments are desired as regards the present vessel. He should also be asked to give particulars of the number and size of chemical fire extinguishers, it being concluded there is no steam smothering apparatus.

Particulars for Register Book:-

Triple Expansion

12½" x 21" x 35" - 26"


1 SB 180 lb.

HS 1620 sq. ft.

MN 88

*Boiler water gauge  
making repairs by  
Cocks 7.50.*

*Steam smothering  
fitted.*



© 2020

Lloyd's Register  
Foundation

14. 3. 49.

008146-008157-0076