

Rpt. 6.

For the information of Surveyors and the Committee only.

Received at

Office.

10

# Lloyd's Register of Shipping.

(Report on Vessel No. \_\_\_\_\_ Port \_\_\_\_\_)

No. 351. SHIP FORGINGS OR CASTINGS.

I have to report that the undermentioned ~~Iron or~~ Steel ~~Forgings or~~ Castings, manufactured by Messrs. Mitsubishi Zosen Kaisha, Ltd., of Nagasaki Works. for the Vessel No. 4 1 0, being built by them. of them. have been inspected by me as set forth below and found to be, so far as can be seen, sound and free from defects.

Mark on ~~Forgings~~ Castings.

Lloyd's  
No. 351.  
R.C.11-7-25.

NAGASAKI. 29th July, 1925.

*K. Crawford.*

	STERN FRAME.	<u>5</u> RUDDER <del>FRAME.</del> <u>Arms.</u>	STEM.
Material*		Cast Steel	
How made		Open Hearth	
Dimensions		As per plan.	
Progress on Inspection		Annealed & while being machined.	
Date when Inspected		<del>27x6x to 30x8x tons</del> 12-5 to 11-7-'25.	
CASTINGS.			
Tests on Standard Test Pieces.			
Tensile Test—		27.6 to 30.8 tons	
Tons per square inch		34.0 to 41.0 %	
Extension per cent.			
Cold Bending Test—		121° to 132°	
Angle <del>110°</del> fracture			
Drop Test—		10 ft.	
Height from ground			
Hammering Test—		Yes.	
If made according to Rules and found satisfactory			

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £

To be paid at



© 2021

Lloyd's Register  
Foundation

\* If of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.