

31 DEC 1943

Rpt. C. 11 (Contd.)

Index No. 28721

28721

Lloyd's Register of Shipping.

Ship's Name "EMPIRE PUMA"

Official No. 167590

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in April, 1940.

All cargo hatchways on weather decks are fitted with locking bars.

A strongly constructed steel companionway has been built over the small hatchway on the port side of the Bridge Deck; fitted with solid wood door closed and secured from both sides; coaming 17" high.

Gunnery accommodation on port side of Bridge tween-decks fitted with 10" diameter side-scuttles having hinged deadlights. Overboard discharges from accommodation are fitted with automatic non-return valves.

Closing appliances on openings in the Bridge after bulkhead are:-

2 openings with portable steel plates with through bolts and made watertight.

1 opening with hinged steel door.


Load Line Certificates altered accordingly.

A. Reid

Surveyor to Lloyd's Register.

Swansea. 24-12-43.

Original placed on board the vessel.

Noted.
31 DEC 1943
A.S.

© 2020

Lloyd's Register
Foundation