

Lloyd's Register of Shipping.

Ship's Name "COLONEL VIELJEUX"

Official No. ---

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in ---

Hatchway and ventilator satisfactorily fitted starboard side weather deck abreast
cross bunker hatch.

SCANTLINGS.

=====

HATCH.

Size of hatch 1.5 x 1.2 meters

Height from deck : .7 metres

Thickness of plate 10 m/m

Deck angles 80 x 80 x 6 m/m

Closing arrangement. Plate with rubber.

Joint and screw hinged bolts

VENTILATOR

Diameter . 3 metres

Height .87 metres

Thickness of plate 6 m/m

Deck angle 80 x 80 x 6 m/m

Closing arrangement :- wood plug with canvas cover.

Edmond Carlane

Fee: 2400,...

Expenses : 150,...

75 Steel
135W
5/7/46

